Imperial College London

Estates Operations

Record Document Process Guidelines

Guidance for the Project Team

(To be read in conjunction with the latest revisions of the Building Fabric and Mechanical & Electrical O&M Technical Guidelines)

REVISION 2.1

Issue Date: September 2021

Revision History

Revision Number	Revision Date	Summary of Changes
Rev 1	February 2016	
Rev 1.1	March 2017	 Updated 4.07 Draft Manuals Review Process Updated 3.0 Responsibilities Updated 5.0 Asset Register Schedule Updated 6.0 Fire Strategy information Updated 7.0 Additional BFM Literature Updated appendices Asset Register process updated
Rev 1.2	Nov 2017	Revised Asset Register process
Rev 2	Jan 2020	 Updated all references of CAD/CAD strategy to BIM or EIR where applicable. added minor works records requirement updated Asset Register process updated job titles and Division titles where applicable general minor updates of text across the document updated Appendix i: Record Document Flow chart removed Appendix iv: Asset Register flow chart
Rev 2.1	September 2021	 Updated 3.0 Updated Project Manager, Technical Author, Principal Designer and Reviewer responsibilities Updated 4.01 Document reference number Updated 4.03 Record document strategy meeting Updated 4.07 draft manuals review process. Updated 9.0 Delivery to relate to digital delivery inclusion of Technical Author's scope of service (appendix v)

Contents

- 1. Introduction
- 2. Record Documents as a deliverable
 - 2.01 Minor Works
- 3. Responsibilities
- 4. Process:
 - 4.01 Document Reference number
 - 4.02 Technical Author Appointment
 - 4.03 Record Document Strategy Meeting
 - 4.04 Record Document Strategy Meeting Agenda
 - 4.05 Strategy Meeting Follow-up
 - 4.06 Content, Reporting & Tracking
 - 4.07 <u>Draft Manuals Review Process</u>
 - 4.08 Instructions for Commenting
 - 4.09 Composition Review
- 5. Asset Register
- 6. Fire Safety Information
- 7. Additional Building Fabric Manual Literature
- 8. drawings
- 9. <u>delivery</u>
- 10. Contacts

Appendix i: Record Document Process Flow Chart

Appendix ii: Sample Strategy Meeting agenda

Appendix iii: Typical example of Tracker

Appendix iv: Sample Issue Memo

Appendix v: Technical Author's Scope of Service

1. Introduction

A record document is evidence of a transaction carried out as part of business activities. In the context of a construction project, record documents are required as evidence of works carried out and delivered as an outcome of the completed project.

Construction project record documents include but are not limited to:

- As built / As Installed drawings and models
- Building Fabric Manual
- Health and Safety File
- Mechanical Services Manual
- Electrical Services Manual
- BEMS Manual
- Fire Safety Information
- Asset Register
- Project Filing¹

This document is to provide guidance to anyone working on a construction project on the Record Documents (O&Ms) procedure. For a specific breakdown of the required format and content of the O&Ms, refer to the separate documents:

- RM07 Production Guidelines for the Building Fabric Manual (incorporating Health & Safety File)
- RM08 Production Guidelines for the Operating and Maintenance Manuals

Refer to Appendix (i) of this document for a flow chart of the Record Document process.

2. Record Documents as a deliverable.

Issue of Record Documents, **produced to Imperial College standards**, is a required deliverable of a construction project. Completion should not be granted until the documents have been approved by the College and issued formally by the Principal Contractor.

In the event of post-completion works, an agreement will need to be made between the Project Manager, Principal Contractor and Estates Records & Archives Officer on delivery of outstanding works' documentation, so as not to adversely affect completion of the O&Ms – this could be an update to the manual issued at completion or issue of an addendum document – and <u>must</u> be confirmed at the Handover meeting.

2.1 Minor Works

For very minor refurbishment works with a limited budget, for example simple redecoration of a single room, flooring replacement in a small area; a record of what was installed and how it should be maintained should still be delivered. For such works, a full building fabric manual may be impractical and instead a Minor Works Installation Record should be completed by the Contractor or Project Manager. If the scope of works is too complex to be itemised in this single page document, then a manual should be produced, the extent of which should be agreed with the Estates Records & Archives Officer when preparing the contractor tenders.

¹ Delivery of Project Filing is not covered in this document. Refer instead to the Estates Records Management Policy Ref: RM09 Record Document Process Guidelines Rev: 2.1 Date: 02/09/2021

3. Responsibilities

The **Contractor**² is responsible for:

- Ensuring that all record documents produced are an accurate record of the completed works.
- Providing all relevant literature and drawings, as produced by themselves, their subcontractors, consultants, and relevant College departments to the Technical Author for record document production.
- Production of a Record Documents Tracking tool and program; and reporting updates at project team meetings.
- Completion of Asset Register, including documenting removed assets, obtaining asset codes from Estates Facilities, and labelling of plant.
- Issuing completed Asset Register to the Technical Author for inclusion with the O&Ms.
- Coordinating delivery of all completed O&Ms and as-built drawings to the Estates Records & Archives Officer for onward distribution.

The **Technical Author** is appointed by the Contractor to:

- Collate literature, text and drawings issued by the Contractor to produce record documents to Imperial College guidelines.
- Undertake collation, production, review submission and escalation requirements as outlined in the Technical Author's Scope of Service (refer to <u>Appendix v</u>)
- Ensure O&Ms have been reviewed by all parties before release of final documents.
- Arrange for delivery of all record documents to the Estates Records & Archives Officer following sign off by Project Manager.

The **Project Manager**:

- Organises the Record Document Strategy Meeting.
- Ensures that the agreed process is adhered to for the duration of the project.
- Carries out early-stage review of initial draft document
- Circulates final draft to relevant College staff for approval
- Undertakes final sign-off review, including confirming that all necessary parties have approved the final drafts, to ensure the documents are an accurate record of works carried out
- Authorises delivery of record documents to the Estates Records & Archives Officer
- Ensuring all record documents have been issued to the College's requirements before giving Completion.

The **Principal Designer** is responsible for:

- Liaising with the Contractor and Technical Author to ensure the Building Fabric manual includes the Health & Safety file, produced as per CDM15 regulations.
- Ensuring the inclusion of Fire Strategy statement and drawing(s).
- Completion of the Health & Safety pro-forma for inclusion in the Operating & Maintenance Manuals.

The **Estates Records & Archives Officer** is responsible for:

- Providing guidance on the production of O&Ms.
- Chairing the Record Document Strategy Meeting.

² The Contractor would in most cases be the Main Contractor but according to the nature of the work may be instead an M&E Contractor.

- Assigning Document Reference numbers.
- Carrying out a final Composition Review of the O&Ms.
- Taking delivery of all completed record documentation for onward distribution.
- Distribution of Issue Memo to confirm receipt of record documents.

The **BIM Manager** is responsible for:

- Checking drawings and data to ensure compliance with the project specific / College EIR.³
- Checking and allocating room numbering.
- Provide guidance on meeting the EIR requirements.

The **nominated reviewers**⁴ are responsible for:

- Reviewing the draft documents.
- Reporting back to Technical Author with comments within the agreed timescale.

4. Process

To ensure a timely and accurate handover of record documents, the production of record documents should follow this process:

4.01 Document Reference number

The expected O&Ms are registered by the Estates Records & Archives Officer upon receipt of the F10, generating a Document Reference number. If notification to the HSE is not required, the CDM Notification document will be the trigger for this process in place of the F10. The Project Manager should ensure a copy of either document is forwarded to the Estates Records & Archives Officer.

The Document Reference number is building and phase specific and is to be displayed on all volumes of the relevant O&Ms with the project number.

If a project is completed in several phases and/or in multiple buildings, separate Document Reference numbers will be assigned for each area of the works, requiring separate sets of record documents. This will be agreed in the Record Document Strategy Meeting.

4.02 Technical Author Appointment

For most projects, the Contractor is to appoint a Technical Author from Estates' recommended list of companies, obtained from the Category Manager (Construction) or from the Estates Records & Archives Officer. The Project Manager and Estates Records & Archives Officer must be notified of the selection.

Technical Authors will provide a standard level of service which ensures a focused and proactive approach to the production of the manuals. Refer to Appendix v: Technical Author's Scope of Service

³ Employers Information Requirement

⁴ Nominated reviewers of the O&Ms are agreed at the Record Document Strategy Meeting and named on the sign-off form. Depending on the nature of the project, this would normally be the Designers and Supervisors.

⁵ Review procedure as agreed in the Record Document Strategy Meeting

For minor projects, if it is agreed that the scope of works does not warrant the appointment of a Technical Author, the Contractor must instead produce the record documents in accordance with the Building Fabric and O&M production guidelines (RM07 and RM08).

This should be agreed when the tender documentation is being prepared to ensure that the Contractor guotes for the appropriate scope of works; any change to this agreement at a later stage should be addressed to the Project Manager and Estates Records & Archives Officer.

The Technical Author should report on a regular basis directly to the Project Manager and Principal Designer, advising them of any potential problems or shortcomings associated with meeting the programme's key dates.

4.03 Record Document Strategy Meeting

The Project Manager is to set up a Record Document Strategy Meeting after the Contractor has been appointed. The following attendees should be invited:

- Project Manager
- Contractor (Site Supervisor and nominated Information Manager/Document Controller)
- Imperial College Estates Records & Archives Officer
- Imperial College BIM Manager
- Imperial College Maintenance Manager for the project area
- Imperial College Building Manager for the project area
- Principal Designer
- Lead Designers from relevant disciplines (must receive minutes if unable to attend)
- Imperial College Fire Officer/Security Officer/Controls Engineer, where applicable to the nature of the project.
- other College representatives or project team member as appropriate to the works

This meeting should take place before the appointment of the Technical Author to enable appropriate pricing of record document production. A follow up meeting may be scheduled with the Technical Author in attendance if required.

4.04 Record Document Strategy Meeting Agenda

The Estates Records & Archives Officer will chair the meeting to address the following items. Refer to Appendix (ii) for Agenda template.

- Introductions
- Scope of works and documents required, ie phased projects, multiple locations, scope of works, specialist manuals.
- Quantity and format of O&Ms
- Summary of contents and required literature.
- Room numbering, required drawings and EIR compliance
- Asset Register
- Fire Safety strategy
- Structural information
- Other items for inclusion.
- Sign off/Review: agree nominated technical reviewers, deadlines, review method.
- Any other queries

4.05 Strategy Meeting Follow-up

The Estates Records & Archives Officer will distribute the meeting minutes to the attendance list, accompanied by a cover email confirming the project number, document reference number, and agreed project title.

The items agreed at the meeting form the scope of works for the Technical Author. For complex projects, a follow up meeting may be required with the Technical Author present.

4.06 Content, Reporting and Tracking

The Principal Contractor or Technical Author must produce a tracking tool to report on the progress of the record documents. This will also include checking for compliance to the EIR (refer to section 8.0 for further details).

The tracker will include all items agreed in the strategy meeting, including a schedule of Manufacturers literature and sub-contractors' drawings, progress of drawings' production and draft O&M's sign-off procedure. An example of a typical tracker can be viewed in Appendix (iii).

Refer to the separate technical guideline documents *RM07 Production Guidelines for Building Fabric Manuals* and *RM08 Production Guidelines for Operating and Maintenance Manuals* for a full outline of the required contents.

Reporting and tracking of record documents' progress should be included on the agenda of project handover meetings.

4.07 Draft Manuals Review Process

Draft copies of the manuals are to be issued in accordance with the Project Handover Plan and allow sufficient time for approval prior to final issue. Unless otherwise specified, the drafts should be uploaded to the College project filing on Box.⁶

The early draft will contain only certain project information compiled at this stage, which should include:

- Scope and location of works
- Project Directory
- Schedules of literature and certificates
- Schedules of drawings (drawing registers)

The literature, drawings or certificates themselves may not yet be available or to be issued for comment under separate cover but the schedule should list what is to be included.

The purpose of the draft at this stage is to ensure that the manual is being set out correctly, that key project information is correct and demonstrates that information for the other sections is in the process of compilation. This early draft should be reviewed by the Project Manager, Designers, Contractor and Supervisors to ensure the documentation will accurately reflect the works carried out.

⁶ do not use file sharing services not authorised by Imperial College ICT such as WeTransfer or Dropbox unless specific agreements have been made, to ensure security of College data.

The first complete draft will be issued by the Technical Author to the Designers and Supervisors for review, along with any other reviewers agreed at the Record Document Strategy Meeting, at an appropriate date to enable reviews to be conducted prior to completion. This draft should include finalised literature and drawings, with notification of any commissioning certificates for insertion at completion. This review must also ensure any changes made to the scope of works since the first draft have been updated and incorporated.

Any comments on missing, incomplete, or inaccurate information should be addressed to the Technical Author to report back to the Contractor. The Technical Author is to compile a tracker of comments, which will be updated when comments are addressed. A copy of the tracker, when completed, should be issued with the completed manuals as a record that the content has been reviewed to the satisfaction of all parties concerned.

The Project Manager should provide the Building Manager, Maintenance Manager, and any other internal interested parties with an opportunity to review the manuals and submit comments before the finalised version is issued. This review is referred to as the "Stakeholder Review"

Following this, the Project Manager conducts the final Sign-off Review, ensuring that all necessary parties have approved the final draft, and a fully hyperlinked draft is sent to the Estates Records & Archives Officer to carry out the Composition Review. Refer to Section 4.09 for a summary of elements comprising the Composition Review.

Refer also to <u>Section 8.0</u> of this document for drawings' review procedure and <u>Section 3.0</u> for an outline of individual responsibilities.

4.08 Instructions for Commenting

The following guidelines should be observed when commenting on the information provided at draft stage:

- It is essential that the text in the draft copy is correct. Additional comments made at final issue due to lack of appraisal of the draft may result in additional costs being charged by the affected party and/or delayed final issue of the documents.
- Comments should be issued in the form of a snagging list, detailing the Section, page, or item number as appropriate, clearly indicating what is required.
- Comments at technical review stage should be concerned with technical accuracy of the
 content. If there are any queries regarding the format or layout of the drafts, then the
 matter must be reported to the Project Manager and Estates Records & Archives Officer
 at the earliest opportunity.
- Suggestions regarding changes to the standard specification for record documents must be approved in a meeting with the Estates Records & Archives Officer, Estates Health & Safety Advisor (Construction), Maintenance Manager and the Project Manager before they can be incorporated. If format, layout, or standard content changes have not been agreed, they will be rejected at the final Composition Review.

To avoid delay at completion, comments and completed forms should be returned promptly. The Technical Author is to escalate any delay in the production process to the Project Manager, which will then be addressed at the project team meeting.

4.09 Composition Review

The composition review is carried out on the final draft hyperlinked pdf version of the manual by the Estates Records & Archives Officer after the technical content has been signed-off.

This review only checks the following:

- Project Number
- Proiect Name
- Document Reference Number
- Hyperlinks
- Adherence to Guidelines
- · Structure and clarity of document.
- Any specific items or exceptions agreed at the Strategy Meeting have been addressed.
- Whether the drawings have been checked/approved for EIR compliance.

Although this review does not cover the technical content, which should have been verified and approved by this stage, any items addressed in the Strategy Meeting which have not been incorporated will be referred back to the Project Manager for clarification.

This completes the review process and must take place before the manuals are produced in their final version in digital and hard copy.

The Estates Records & Archives Officer will also review the format and layout of the manual at an earlier stage where required but is not involved in the technical content reviews.

5. Asset Register

A register of newly installed maintainable Mechanical and Electrical Assets within the project area is to be included within the record document issue.

Refer to this page for further details on the Asset Tagging process: http://www.imperial.ac.uk/estates-facilities/buildings/procedures/assets/

This process applies to any project where mechanical or electrical assets are removed, updated or installed. For minor works projects, where the M&E information is incorporated with the Building Fabric manual, the asset register should form a part of this file and the above process is to be followed.

6. Fire Safety information

All fire safety information is required to comply with Building Regulation 38 and as outlined in Appendix G of Approved Document B. The Contractor is responsible for providing this information as part of the project completion record documents.

The overall format and scope of fire safety record information should be confirmed at the Record Document strategy meeting. For complete new build projects, a full fire safety manual conforming to the above building regulation should be produced and issued to the Head of Fire Safety (via the Estates Records & Archives Officer as part of the record document process)

For refurbishment projects, fire alarm information is included in the Electrical O&Ms (*note that a new fire alarm panel install requires its own manual*) and fire safety information is in the building fabric manual. The exact scope of this information would be appropriate to the nature of works, in accordance with legislative requirements and could include, for example:

- Fire strategy drawing(s) and statement⁷
- Compartmentalisation drawings

Section 4 of the Building Fabric manual should detail where the appropriate information is located. Upon receipt of the Issue Memo, the Head of Fire Safety can refer to this section to locate the required information to update their building records.

7. Additional Building Fabric Manual Literature

The following items may also be required for the building fabric manual, in accordance with the nature of the project and should be agreed at the Record Document Strategy Meeting:

- Planning Consents
- Asbestos Reports
- surveys and reports
- Waste Management final report
- F10 Notification to the HSE
- Consent to Commence Work
- Imperial College specialist works (if installed/carried out during the contract period)
- Building Control Certificate

Refer to *Production Guidelines for the Building Fabric Manual (incorporating Health & Safety File)*RM07 for full details of expected literature for the manual.

8. Drawings

All drawings, models and digital information are to be issued as final As-built / As-installed status and produced to the College's Employers Information Requirements (EIR). Refer to the project specific EIR for information and deliverables.

The information approval process is as follows:

- Room numbering is to be allocated at Stage 3 (Design) by the College Building Information Manager and is to be correctly recorded on all drawings and digital information from this stage.
- The Design Team send sample drawings to <u>cadcompliance@imperial.ac.uk</u>, at Stage 3, for the BIM Manager to check on project EIR compliance. The email MUST include the project number in the heading.
- Towards the end of Stage 5 (Construction), the Contractor sends sample final As-built /
 As-installed drawings to cadcompliance@imperial.ac.uk (the email MUST include the project number in the heading), for College approval before record documents can be issued.
- Drawings and digital information to be issued in native (.dwg or.rvt) format and PDF.

⁷ where no current Fire Strategy drawing exists, the Contractor should produce new drawings outlining the fire strategy of the works area. This should be delivered as an as-built drawing in line with the Project EIR

 A set of hard copy drawings are to be printed to the size specified on the scale, folded down to A4 for insertion into the appropriate manual.⁸

All models and drawings must adhere to the project specific EIR where they inform on the fabric, infrastructure, and services of the building (for example, architectural, structural, mechanical, electrical, public health) and may be needed for alterations or renovations in the future.

Some manufacturers' component drawings, supplied in *Section 9 Manufacturer's literature* of the Building Fabric Manual, are issued for information purposes only and may not require full compliance. The Estates Records & Archives Officer must be included in this decision, to confirm what information is needed for the Estates Archive.

9. Delivery

The Project Manager is to ensure that all record documents are delivered to the Estates Records & Archives Officer for onward delivery to the agreed recipients.

Unless otherwise specified, the final digital format documents are uploaded to the College project filing on Box, notifying the Estates Records & Archives Officer.

The digital upload of final documentation must be accompanied by a sign-off form/letter or the completed Comments Tracker stating that the files have been completed according to Imperial College requirements and are an accurate record of works completed.

One set of hard copy manuals and drawings are delivered to the Estates Records & Archives Officer.

The Estates Records & Archives Officer will check the received records comply with that agreed at the Composition Review and send an Issue Memo to confirm delivery. The distribution list consists of the Building Manager, Maintenance Manager, Project Manager, Contractor and Construction Safety Manager and other interested parties within Imperial College. Following receipt of Issue Memos for all agreed O&Ms, the Project Manager can issue the Completion certificate.

The College will not take delivery of partially completed/not signed off record documents.9

⁸ Refer to documents RM07 Production Guidelines for the Building Fabric manual and RM08 Production Guidelines for Operating & Maintenance Manuals for more information regarding delivery formats.

⁹ A procedure for post-completion works needs to be agreed at a meeting in advance of completion, so as not to delay the issue of record documents.

10. Contacts

For further information please contact the following:


Record Documents: Estates Records & Archives Officer Alyson Brewer <u>a.brewer@imperial.ac.uk</u> +44(0)20 7594 6483

Drawings, models and digital information: Building Information Manager. Julie Neville <u>j.neville@imperial.ac.uk</u> +44(0)20 7594 8896 Sample drawings for EIR compliance check to: <u>cadcompliance@imperial.ac.uk</u>

Health & Safety Information: Health & Safety Advisor (Construction) Oluseyi Oduntan o.oduntan@imperial.ac.uk +44 20 7594 8936

Asset Registers: Estates Operations' Customer Service Centre. eo.csc@imperial.ac.uk +44 (0)20 7594 8000

Annandiy is Bassed Decument Draces flow short
Appendix i: Record Document Process flow chart.
refer to the following page



Appendix ii: sample Record Document Strategy Meeting agenda
Refer to following pages.

	Record Document Strategy	Checklist
Project Num	mber: Project Tit	le:
Project Mana	nager: Location	
Project Stag	ge: Meeting D	ate:
Distribute fo	for review / comment / information / action to:	
Project Mana	nager	
Principal De		
Principal Co		
Building Mar		
Maintenance		
	Archives Officer, Imperial College	
	ger, Imperial College	
M&E Contra		
Technical Au	Author	
Lead design	From relevant disciplines	
Jacktional Co	Tolle staff or project team,	
as a police w	le to the project.	
• 0	May Then -	
	Cha Cill ha	
	"Ana" "Ot for	
	190 at 1 10r	10
	at time	19.6
Checklist	"'/6 o	£ .
Please read the Please return and recomme	through the following and add your responses. In this to the Records & Archives Officer who will addressed to the Comment section.	d any further compents, requirements
1	O&M Guidelines. Please confirm you have the I	atest version and that the manuals
	will be produced in accordance with the guideline	
	Guidelines available to download from this page	
	projects/project-procedures/processes/project-m	anagement/record-document-
	strategy/	
	or from https://www.imperial.ac.uk/estates-projection	cts/space-management/information-
	management/	
Response		
0	D. Contractivity in the Land of the Land	dia a bassa Pala
Comments	Refer to guidelines in contract or download from	the above links.
2	Has a Technical Author been appointed to collat	•
	current recommended Technical Authors, familia	ar with our record document
	requirements are:	
D	•	
Response Comments		
3	Scope of works. Please provide a brief outline of	f the works and areas affected
Response	1	
Comments		
4	Project Start on site date	

Response		
Comments		
5 Raponse	is distinct)	ation issued for each phase ors are appointed or if each area of works as each phase completes (recommended rseded services installations)
Man.	7/0	
Comments 6	Do any element of the works take place in other buildings or locations? Any works taking place on the roof Any works taking place in orantroof External areas delevations? *Separate manuals may be regulired if work ** personal fall protection equipment alough 7883:2019).	s aled Sing place in other buildings
Response		sentation requirements to be agreed (BS) Of Oeting
Comments		4779
7	Scope of M&E Works – major or minor? If very minor, this information can be included manual (refer to guideline document RM07) be produced (guideline document RM08)	
Response		
Comments		
8	Quantity and format of manuals is outlined manual Guidelines and Section 11 of RM08 Are there any additional copies required (for interest in the location)?	B O&M manual guidelines.
Response:		
Comments		
9	Drawings and digital information must be p EIR (Employers Information Requirements) 1. has an EIR been produced and iss 2. Have sample design stage drawing (cadcompliance@imperial.ac.uk) to Note that final drawings must be as-built sta- carried out, via the Technical Author where	ued for this project? gs been sent to Julie Neville confirm compliance to the EIR? atus and a final compliance check must be
Response:	1.	
Comments		
9a	Anticipated drawings and/or model delivera	
	□2D Architectural □2D Electrical □2D Mechanical □2D Fire	□3D Architectural □3D MEP □3D Structural

	□2D Structural
	□Other:
10	Are there any changes to room layouts and have new room numbers been allocated
	by Julie Neville, Building Information Manager?
Response:	
Comments	
11	Asset Register
	Are existing maintainable assets being removed or replaced?
	Are new maintainable assets being installed?
	Refer to RM09 Record Document Process guidelines and
_	http://www.imperial.ac.uk/estates-facilities/buildings/procedures/assets/
Response:	
- Amanta	DM to get current register for works area. contact Estates Operations Customer
	Sorving Contro (EOCSC) to request the current asset ashedule
7	Dervice Centre (EOCSC) to request the current asset schedule.
16t~	Check to comoved assets and cross them off the list (do not delete from list)
\ _,\d\\\c	New assets terralisted on a separate enreadsheet downloadship from the shove link
	PM to get current register for works area – contact Estates Operations Customer Service Centre (EOCSC) to request the current asset schedule. Okst@imperial.ac.uk Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the listed on a separate spreadsheet downloadable from the above link. PM Check of emoved assets and cross them off the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not delete from list) New assets to the list (do not d
	Control of Column before Donal issue the final acceptance and Countries
	Contractor to apply tags before HO and issue the final asset register and 2x photos of
	each asset as part of the final record opcurrent deliverables
10	Refer to link above for wildetans at the asset register process
12	Are there any structural alterations taking place of the surveys been conducted on
	the structure? What reports and drawings will be included in the manual?
Response:	$O_{I} M_{2}$
	"1'COt:_
Comments	the structure? What reports and drawings will be included in the manual?
	9
13	Any other reports or surveys conducted in the works area or connecting services?
Response:	
Comments	
14	Schedule of Manufacturers Literature.
	Please refer to section 4.06 of guideline document RM09 Record Document
	Guidelines and confirm that a schedule will be produced at an early stage to collate all
	relevant literature (refer also to guideline documents RM07 and RM08 for details on
	the literature required)
	Please include any queries you may have on what literature is required.
Response	
Comments	
15	Are there any items procured by Imperial directly which are to be installed during the
	project programme?
Response	
•	
Comments	
16	Are there any specialist items procured within the contractor's scope?
.0	Which manual are they to go in (Building Fabric, Mechanical, Electrical) or issued as
	a standalone manual (as an exception only, refer to guideline document)?
	a statistic manual (as an exception only, role to galdeline decamony)
Response	
. 100001100	
Comments	
Comments	

17	Are new or additional wireless access points being installed?
Response	
Comments	if a survey is to be conducted by ICT on Wi-Fi range, please include this in section 8/7
Exam	of the manual. Confirm with project manager if survey will be taking place. If yes but report isn't ready by the time the manual is completed, please reference it in this section noting that it is to follow by separate issue direct to the Estates Records
	Officer.
etails	Are new or additional wireless access points being installed? if a survey is to be conducted by ICT on Wi-Fi range, please include this in section 8/7 of the manual. Confirm with project manager if survey will be taking place. If yes but report isn't ready by the time the manual is completed, please reference it in this section noting that it is to follow by separate issue direct to the Estates Records Officer. Officer. Will the fire safety strategy change as an outcome of the works? 2. Will the fire strategy drawings been produced or any other relevant docume fation? Is a new fire form ranel or system being installed or an update to the except system? Other items: 1. Final SWMP report 2. Planning 3. Warranties – specialist, extended or with conditions attached?
Response:	9e at tip USe
Comments:	of m
19	Other items: 1. Final SWMP report 2. Planning 3. Warranties – specialist, extended or with conditions attached?
	 Building control Notifiable to HSE (F10 issued) Any other project specific H&S requirements? Building logbook Separate H&S file (refer to RM07, usually incorporated within the Building
Response	Fabric Manual)
20	Sign off and review:
20	1. Completion date 2. O&M delivery date 3. Review method 4. Reviewers (see Q21 and 22) Refer to guideline document RM09 for O&M review process and responsibilities
Response	1.
21	Principal designer for the construction period
response	
Comments	If Imperial College is retaining the role of Principal Designer, the Project manager needs to name the responsible person who is undertaking that role. The named person is then responsible for liaising with the Project Manager, Contractor and relevant parties within Imperial to produce the H&S documentation for inclusion within the manual.
22	 External supervisors with record document review responsibility? Designers novated to the Contractor? Do the Designers have record document review responsibility?
response	' '
23	Any other items?
Response	
Comments	

Rev: 31/08/2023

Appendix iii: typical example of Tracker

Refer to following page

O&M Tracker

Project Name:

Report Date: Wed 12/08/15

Fri 29/05/15

ICZZ1701

Project No:

XXX

				Date										
Work section	Сопитасног	Draft Issued to Contractor (Enter dates)	Contractor Review and issue to consults / ICL / TA	Consults / ICL Review and Return to Contractor	Contractor returns to lacknical Author for lamendments	Principal Designer Review and if Return to Contractor	Technical Author amends and issues to PM	PM Final review and comment	FLOAT (working fi	Contractor assembles	Contractor issues final draft pdf to Imperial College Archives Officer (projects)	Imperial College Archives Officer (Projects) - composition review.	Final Changes by Contractor	Contractor issues FINAL to ICL Archive
Activity days			3	5	2	5	2	2	Ī		3	2	2	2
Mechanical Manual	oontractor name	Current Production Stage: Awaiting into for draft Draft in Production Comments Received, Avaiting Comments Received, And Archartin In Production Manuals Issued Action/Info Needed from (this Yes Services Contractor Yes Services Contractor No Main Contractor No CDMC No CIENT	Awaiting info for dark Awaiting info for dark Draft in Production Draft issued, Awaiting Comments Comments Received, Awaiting Documents Finals in Production Manuals Issued Minito Needed from (this will change as jo Services Contractor Services Contractor Common	Current Production Stage- Awaiting thic for draft Draft in Production Draft issued, Awaiting Comments Comments Received, Awaiting Documents Answers Received, Awaiting Documents Finals in Production Manuals Issued Action/Info Needed from (this will change as job progresses) Yes Services Contractor Yes Services Contractor No Man Contractor No Collect No Client	. .									29/05/2015
Electrical Manual	contractor name	Current Production Stages. Awaiting into for draft Draft in Production Draft Issued, Awaiting Comments Received. Answers Received. Answers Received. Answers Received. Andurals is production Manuals Issued Action/info Needed from (thi Yes Services Contractor Yes Services Contractor No Main Contractor No Client No Client	an Production Stage: Awaiting into for draft Draft in Production Draft issued, Awaiting Comments Comments Received, Awaiting Documents Finals in Production Manuals Issued Aninfo Needed from (this will change as joe Services Contractor Services Consultant Main Contractor CDMC Client	Current Production Stage- Awaiting into for draft Draft in Production Draft issued, Awaiting Comments Answers Received, Awaiting Documents Finals in Production Manuals Issued Action/Intro Needed from (this will change as job progresses) Yes Services Contractor Yes Services Contractor Yes Services Consultant No Main Contractor No CDMC No CIIent	.									Fri 29/05/15
BMS	contractor name	Mon 13/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15	Thu 21/05/15	Mon 25/05/15	Wed 27/05/15	Fri 29/05/15
Building Fabric Manual (examples provided for the purpose of this sample document)														
Façade and Glazing, fire exit door	contractor name	Fri 24/04/15	5	Wed 06/05/15	Fri 08/05/15	Fri 15/05/15	Tue 19/05/15	Thu 21/05/15	-4.00	Mon 18/05/15				
Grazed doors and screens, me rated, partitions Folding doors	contractor name	Fri 10/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
Folding door steelwork	contractor name	Wed 15/04/15	Mon 20/04/15	Mon 27/04/15	Wed 29/04/15	Wed 06/05/15	Fri 08/05/15	Tue 12/05/15	2.00	Mon 18/05/15				
Decorations	contractor name	Fri 10/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
Floor finishes	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Ceilings	contractor name	Wed 15/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
Ironmongery	contractor name	Wed 15/04/15	Mon 20/04/15	Mon 27/04/15	Wed 29/04/15	Wed 06/05/15	Fri 08/05/15	Tue 12/05/15	2.00	Mon 18/05/15				
Wall panelling from WC Fields	contractor name	Mon 06/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15	Thu 21/05/15	Mon 25/05/15	Wed 27/05/15	Fri 29/05/15
Stud Walls, Plasterboard and miscellaneous builders items	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Tea point and sinks (including cleaners)	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Granite Slabs	contractor name	Fri 17/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
Glass wipe board	contractor name	Wed 15/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
Fire stopping and intumescent coatings	contractor name	Wed 15/04/15	Thu 16/04/15	Thu 23/04/15	Mon 27/04/15	Mon 04/05/15	Wed 06/05/15	Fri 08/05/15	7.00	Mon 18/05/15				
GDO AHU external Steelwork	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				

O&M Tracker

Project Name:	xxx	Project No:	ICZZ1701	Completion Date	Fri 29/05/15								Report Date:	Wed 12/08/15
Work section	Contractor	Draft Issued to Contractor (Enter dates)	Contractor Review and issue to consults / ICL / TA	Consults / ICL Review and Return to Contractor	Contractor returns to lackning to lackning all Author for lamendments (Principal Designer a Review and is Return to Contractor	Technical Author F amends and issues to PM	PM Final (comment	FLOAT Construction (working find days)	Contractor assembles G final DRAFT II A A (I)	Contractor issues final draft pdf to Imperial College Archives Officer (projects)	Imperial College Archives Officer (Projects) - composition	Final Changes by Contractor	Contractor issues FINAL to
Activity days			3	5	2	5	2	2			8	2	2	2
AV Manual	contractor name	n/a/	n/a/	n/a/	n/a/	r/a/	n/a/	Fri 15/05/15	2.00	Mon 18/05/15				
Drawings (compliance with CAD strategy required, must be submitted to College CAD team for approval) Examples provided for the purpose	submitted to College CAD t	eam for approval)	Examples provide		of this sample document only	ment only								
Furniture Layout	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Builderswork	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Reflected Ceiling Plan	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Finishes Layout	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
South Elevation	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
North Elevation	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
West Elevation	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
East Elevation	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Section BB	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Section CC	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15	TF:: 04/06/46	Mon OF JOE 14F	THE POLICE TO THE	7,100,00
Proposed Section EE and FF	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15	01/00/13 11/00/13	WIOTI 23/03/13	wed 27/03/13	61/60/67113
Fire Strategy	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Structural Drawings	contractor name	Fri 17/04/15	Wed 22/04/15	Wed 29/04/15	Fri 01/05/15	Fri 08/05/15	Tue 12/05/15	Thu 14/05/15	3.00	Mon 18/05/15				
Mechanical Drawings	contractor name	Fri 10/04/15	Wed 15/04/15	Wed 22/04/15	Fri 24/04/15	Fri 01/05/15	Tue 05/05/15	Thu 07/05/15	8.00	Mon 18/05/15				
Electrical Drawings	contractor name	Fri 10/04/15	Wed 15/04/15	Wed 22/04/15	Fri 24/04/15	Fri 01/05/15	Tue 05/05/15	Thu 07/05/15	8.00	Mon 18/05/15				
Specialist Drawings	contractor name	Fri 24/04/15	Wed 29/04/15	Wed 06/05/15	Fri 08/05/15	Fri 15/05/15	Tue 19/05/15	Thu 21/05/15	-4.00	Mon 18/05/15				
									H					
Other (Examples provided for the purpose of this sample document only)	ocument only)													
For Section 8 of the manual: Brief description of AV equipment installed that is not included in xxx's work	contractor name	n/a/	n/a/	n/a/	n/a/	n/a/	n/a/	Fri 15/05/15	2.00	Mon 18/05/15				
Add Asbestos advice to manual.	contractor name	n/a/	n/a/	n/a/	n/a/	r/a/	n/a/	Fri 15/05/15	2.00	Mon 18/05/15				
						1	1	†	1	1				
						1	1	+	†	1				
						1		\dagger		1				
								†		T				
								†		T				
									1					

Appendix iv: sample Issue Memo

refer to following page

Imperial College London

Estates Operations Imperial College London Level 5, Sherfield Building South Kensington Campus Tel: +44 (0) 207 594 6483 www.imperial.ac.uk

Alyson Brewer Records and Archives Officer

MEMO

To:- Building Manager

From:- Alyson Brewer

CC:-

Maintenance Manager
 Project Manager
 Senior Supplier/ Project Manager
 Principal Contractor
 issue memo distribution list

+ ISSUE MEMO distribution is

Date: 19/03/2021

Project No:- insert project number

insert document reference number and project title

Receipt of digital format Building Fabric manual and O&Ms

Dear all,

The following documents, associated with the above project, have been issued in digital format on [date]. PDF formats can be accessed via the following links by all Estates staff. Please advise if access is needed for anyone else.

- Building Fabric Manual and architectural drawings: https://imperialcollegelondon.box.com/s/cgukfzoxubrdbxcfp7q9tzcot06j3xx
- 2. Mechanical Services Manual and mechanical drawings: https://imperialcollegelondon.box.com/s/tm5xrl7elzv4etqk3jarehg9yubkasmxxb
 - Electrical Services manual and electrical drawings: https://imperialcollegelondon.box.com/s/t243zwda2qsn1qz879o7otfu1fs9e24xxn

The as-built GAs are in the project file, for the CAD team to pick up: https://imperialcollegelondon.box.com/s/36x8y4xpuqq8r9jlec0pkun5no48d8hxxa

A full set, including dwg drawings has been retained in the Estates digital archive. Please contact me if you need a copy of the dwgs.

Hard copies of the manual and drawings will be delivered to the Estates Archive

Best Regards, Alyson Brewer Estates Records & Archives Officer

Appendix v: Technical Author's Scope of Service refer to following page

Technical Author Specific Scope of Service

September 2021



TECHNICAL AUTHOR SCOPE OF SERVICE

Imperial College London's (ICL) scope of technical author services is intended to provide a standard approach through each project process to completion. Further details of the College's Project Process and Procedures are included in the Projects part of the Imperial website in Project Procedures / Process Map.

This document must be read in conjunction with ICL's Consultant's Core Duties document and the Design Responsibilities Matrix.

The technical author duties are arranged over various stages, as outlined below.

These stages generally follow the RIBA stages. There is some repetition of particular services between different stages.

0	Strategic Definition: Project initiated using Client Brief and Business Case. Obtain information on the site, surveys and appointing consultants and carry out Feasibility Studies.
	Project Approval: Approval of capital funding for the project at Imperial College Project Review meeting (PRM)
1	Preparation and Brief: Development of Design brief with users and technical advisors.
2	Concept Design: preparing and approving concept design.
3	Developed Design: scheme and design development, plus obtaining statutory approvals.
4	Technical Design: Detail technical design and specifications plus statutory approvals. Preparation of design details and further information for construction as required by construction contract.
5	Construction: mobilization, reviewing and inspecting the works
6	Handover and Completion: Post Construction: final inspections and accounts

STAGE 0 – 3

PROJECT DUTIES:

1. No duties; technical author will be procured at the end of Stage 4.

STAGE 4 TECHNICAL DESIGN

PROJECT DUTIES:

1. No Duties, the Technical Author will be procured at the end of Stage 4.
A record document strategy meeting will take place with the Contractor, Estates Records & Archives Officer, Estates BIM Manager and Project Manager, the minutes of which will be forwarded to the Technical Author to assist with and provide clarification during their tender process.

STAGE 5 CONSTRUCTION

PROJECT DUTIES:

1.	Contact the Estates Records & Archives Officer to confirm the document reference number and project number/name
2.	Attend record document requirements meetings if requested by the Contractor to discuss what was agreed at the initial strategy meeting.
3.	Request and collate the required information from the Contractor; record status and actions in a tracker document and report as part of a RAG report.
4.	Compile/author the information to produce draft sections that adhere to the College guidelines (RM09 Record Document Guidelines, RM08 Operation and Maintenance Manual Guidelines and RM07 Building Fabric Manual Guidelines).
5.	Follow any project-specific requirements documented in the O&M/Record Document Strategy Meeting
6.	Send draft information to the agreed signatories for comments (as frequently as required).
7.	Incorporate the comments into the draft documentation ensuring guidelines (RM09, RM08 and RM07) are followed.
8.	Review a selection of sample drawings across each discipline to ensure they are As-built and that the naming conventions and the Imperial College title blocks/sheets have been used, before sending to the Building Information Manager to ensure EIR compliance.
9.	Feedback EIR comments to relevant parties to ensure any changes are made.
10.	RAG (red, amber, green) report to the Contractor and Imperial College on the progress of manuals and reviews to track performance against planned progress. Where necessary, escalate any delay to the Project Manager.
11.	Liaise with the Principal Designer to Incorporate the health & safety file within the building fabric manual.
12.	Liaise with the Contractor to ensure the asset register is included with manuals.
13.	Cross reference across manuals where necessary (including specialist manuals).
14.	Attend project handover planning meeting where requested by the Contractor to agree dates of key tasks during the commissioning to Completion phase.

STAGE 6 HANDOVER AND CLOSEOUT

PROJECT DUTIES:

1.	Send the final draft manuals to the named reviewers as agreed at the record document strategy meeting, accompanied by the comments tracker for review and sign-off.
2.	Ensure all literature is incorporated within the manual and produced as a fully hyperlinked pdf file
3.	Send the finalised hyperlinked pdf manual and associated drawings and asset register to the Estates Records & Archives Officer for composition review.
4.	Produce the final manuals once the Composition Review is complete with no further comments and the Project Manager has checked and confirmed that all necessary parties have approved the final drafts.
5.	Deliver the final digital copies via the agreed method and the Archive hard copy to the Estates Records & Archives Officer accompanied by a completed comments tracker and sign-off sheet/letter.